



M E M O R A N D U M
PROC #23-19

NOTICE TO BIDDERS

CLARIFICATION NO. 2

SENT VIA E-MAIL

DATE: August 9, 2023
TO: **POTENTIAL BIDDERS**
FROM: Margaret M. Maddalena, Contract Administrator
RE: **CONTRACT #2112 WSPS HVAC REPLACEMENT PROJECT**

Question #1 There are no specs on the supply and return ducts for the rooftop units, should we figure 2" rigid board with Venture clad?

Response: ***The existing supply duct from the rooftop units shall be reused and is uninsulated. Any modification needed to the existing return ducts shall use rigid board.***

Question #2 In the mechanical room are we to use rigid board or wrap for the duct work?

Response: ***Wrap shall be used on any ductwork in the mechanical room.***

Question #3 The breeching is PVC, can we assume no insulation.

Response: ***The breeching is not PVC, it is metal. Refer to Drawing M105 Key Note #9 for breeching specifications.***

cc: Tim Eustace, Executive Director
 Maria Alliegro, P.E., LEED AP, Director of Engineering
 Paul Serillo, Director of Facilities
 Chris Clamser, Engineering Project Manager