

**Attachment A**  
**Request for Proposal Form**  
**Technical Specifications**  
**NJDWSC Shooting Range Remediation Project**

Pay Item	Item Description	CBS Reference	Unit	Unit Cost	Quantity	Total Cost
1.0	Health, Safety and Emergency Response	01352	LS		1	\$ -
2.0	General Conditions					
2.1	Project Coordination and Meetings	01312	LS		1	\$ -
2.2	Construction Photographs and Video	01321	LS		1	\$ -
2.3	Construction Schedules (Progress Schedules and Reports)	01325	LS		1	\$ -
2.4	Required Submittals	01330	LS		1	\$ -
2.5	Contractor Quality Control	01450	LS		1	\$ -
2.6	Temporary Facilities and Controls	01500	LS		1	\$ -
2.7	Mobilization	01505	LS		1	\$ -
2.8	Security Procedures	01356	LS		1	\$ -
2.9	Field Engineering and Survey Control	01720	LS		1	\$ -
2.10	Project Closeout Procedures/Demobilization	01770	LS		1	\$ -
2.11	Project Record Documents	01789	LS		1	\$ -
3.0	Site Preparation					
3.1	Environmental Protection Procedures	01354	LS		1	\$ -
3.2	Site Clearing and Grubbing	02231	LS		1	\$ -
3.3	Soil Erosion and Sediment Control Installation	02370/02150	LS		1	\$ -
3.4	Support of Excavation Installation	04116	LS		1	\$ -
4.0	Protection of the Work and Property	02220	LS		1	\$ -
5.0	Excavation					
5.1	Removal of Concrete pad	02350	LS		1	\$ -
5.2	Removal of Contaminated Soil (Non-Hazardous)	02350	LS		1	\$ -
5.3	Removal of Contaminated Soil (Hazardous)	02350	LS		1	\$ -
5.4	Installation of Dewatering	02350	LS		1	\$ -
6.0	Earthwork	02300	LS		1	\$ -
7.0	Material Handling and Management					
7.1	Supply and handling of imported backfill material for the excavation areas	02110	CY		2,495	\$ -
7.2	Supply and handling of imported vegetative cover material in restoration areas	02110	CY		710	\$ -
7.3	Treatability Study Analysis	02110	LS		1	\$ -
7.4	Characterization, Transportation and Off-site Disposal of Impacted Soil (Non-Hazardous)	02110	Ton		3,458	\$ -

**Attachment A**  
**Request for Proposal Form**  
**Technical Specifications**  
**NJDWSC Former Shooting Range Remediation**

Pay Item	Item Description	CBS Reference	Unit	Unit Cost	Quantity	Total Cost
7.5	Characterization, Transportation and Off-site Disposal of Impacted Soil (Hazardous)	02110	Ton		150	\$ -
7.6	Characterization, Transportation and Off-site Disposal of Spent Liquid Waste including Dewatering Fluids, Decontamination Liquids and Rinse Water (Non-Hazardous)	02110	gallons		30,000	\$ -
7.7	Characterization, Transportation and Off-site Disposal of Spent Liquid Waste including Dewatering Fluids, Decontamination Liquids and Rinse Water (Hazardous)	02110	gallons		100	\$ -
7.8	Characterization, Transportation and Off-site Disposal of debris including bulk concrete selected off-site disposal facility	02110	Ton		15	\$ -
7.9	Transportation and off-site disposal of solid waste (including PPE, disposal sampling equipment, silt fence and liner materials)	02110	Ton		20	\$ -
8.0	Dust Control	01560	LS		1	
9.0	Site Restoration					
9.1	Site Restoration	02800/02150	LS		1	\$ -
9.2	Exterior planting in wetland, herbivory control and one-year guarantee	02930	LS		1	\$ -
<b>TOTAL COST</b>						<b>\$ -</b>

<b>Additional Line Items</b>						
I	Contingency for Additional Excavation	02350	CY		1	\$ -
II	Treatment of Contaminated Soils On-site	02110	ton		1	\$ -
III	Screening of Contaminated Soils On-site	02110	ton		1	\$ -

Notes/Abbreviations:

LS Lump sum  
CY Cubic Yards  
ft. feet

Assumed 1 CY = 1.5 tons

\_\_\_\_\_  
Company Name

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Date

\_\_\_\_\_  
Printed Name

Schedule Recap:

**Non - Mandatory Site Walk: Tuesday, November 19, 2019**

**Questions Due: Tuesday, December 3, 2019**

**RFP Due: Thursday, January 16, 2020**

**Work is anticipated to begin on or about June 2020**